BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

Schedule B

Name of Work: Reserve Fund for Emergency Works Bagalagunte Ward No 14

Sl No	Description of work	Unit	Qty	Sanctioned Approved Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work	Cum	23.96	1500.00	Rupees One thousandFive hundredonly
	Cleaning the existing WBM road surface including removing all binding materials and other foreign matter with wire brushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air, to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications, MORTH specification clause 501	Sqm	166.26	18.00	Rupees Eighteen only
	Providing and applying primer coat with S.S. Bitumen emulsion on prepared surface of granular base such as WBM, WMM including clearing of road surface and spraying primer coat @ rate of 0.6 kg / sqm using mechanical means complete as per specifications, with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Sqm	166.26	29.00	Ruppes Twenty nine only
	Providing and applying tack coat using 80/100 grade bitumen VG 10 on the prepared black topped surfaces at 2.5 kg per sqm heating bitumen in boiler fitted with spray set including cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications MORTH Chapter 5	Sqm	166.26	8.00	Rupees Eight Only

Executive Engineer

Sl. No	Description of work	Unit	Qty	Sanctioned Approved Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
5	Supplying, placing & compacting ready made cold bituminous pothole patching mix in accordance with IRC 116-2014 in 50 kg plastic sturdy bags. The mix shall contain at least 5.6% MC 800 cutback Bitumen & suitable anti-stripping agent. The mix shall be workable for at least 6 months	Bags	293.00	285.00	Rupees Two hundred eighty Five Only
6	Supply of the Labour Heavy Mazdoor to the required place as per the direction of the engineer in charge Complete as per Specification, and as per direction of Engineer-in charge.	Day	48.00	4500.00	Rupees Four thousand Five hundred Only
7	Supply of the Labour Heavy Mazdoor to the required place as per the direction of the engineer in charge Complete as per Specification, and as per direction of Engineer-in charge	Day	480.00	425.00	Rupees Four hundred tewnty five Only
8	Tractor 50 HP on hire basis including Tractor Driver with Helper to carryout the works on emergency as per the direction of Engineer-in-charge of the work	Day	48.00	2300.00	Rupees Two thousand three hundred Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Executive Engineer